



## Title: Thermal Resistance (R-Value) Test Results

### Product: 1" Envirocoustic Wood Wool

Application: Ceiling or Wall

Testing Standard: ASTM C518-21

Test Date: 05/19/2022

*Why this test:* This test determines the thermal resistance, commonly known as the R-Value, of the product. The product is placed between two plates, one cold and one hot, which measure the heat flow to determine the thermal conductivity (k-Value) and thermal resistance (R-Value). This is repeated for 3 samples of the product, the average being the reported R-Value. The values determined by this test satisfy R-Value regulations for insulation materials (i.e. US Federal Trade Commission's "R-Value Rule" (10 CFR 460).

Test Result Summary: R-Value 2.32

Test Specimen ID	Sample Name	Avg. Heat Flux (Btu/hr·ft <sup>2</sup> )	Avg. Thermal Conductance (C) (Btu/hr·ft <sup>2</sup> ·°F)	Avg. Thermal Resistance (R) (hr·ft <sup>2</sup> ·°F/Btu)	Avg. Thermal Resistivity (r) (hr·ft <sup>2</sup> ·°F/Btu-in)	Apparent Thermal Conductivity (k) (Btu-in/hr·ft <sup>2</sup> ·°F)	Specimen Avg. Thickness (inches)	†Specimen Avg. Density (Lbs/Ft <sup>3</sup> )
1	Sample 1	21.63	0.432	2.31	2.35	0.425	0.983	21.63
2	Sample 2	21.95	0.438	2.28	2.33	0.429	0.978	21.90
3	Sample 3	21.21	0.424	2.36	2.39	0.418	0.985	22.85

Test ID: N6822.01-116-25

#### ASI TEST RESULT DISCLAIMER

ASI makes every effort to ensure the accuracy and reliability of the information provided. Laboratory testing is conducted by independent testing organizations. ASI does not guarantee that field tests or independent tests will not vary.

©2022 ASI

# ASI HEAT FLOW METER TEST REPORT

## SCOPE OF WORK

CEMENTITIOUS WOOD FIBER ACOUSTIC PANEL - 1" THICK - ASTM C518

## REPORT NUMBER

N6822.01-116-25 R0

## TEST DATE

05/16/2022 to 05/17/2022

## ISSUE DATE

05/23/22


## PAGES

9

## DOCUMENT CONTROL NUMBER

RT-R-AMER-Test-7906 (01/17/22)

©2017 INTERTEK



**TEST REPORT FOR ASI**

Report No.: N6822.01-116-25 R0

Date: 05/23/22

**REPORT ISSUED TO**

**ASI**

123 Columbia Court North  
Chaska, Minnesota 55318

**SECTION 1**

**SUMMARY**

**SERIES/MODEL: Cementitious Wood Fiber Acoustic Panel - 1" Thick**

Architectural Testing, Inc. (an Intertek Company), dba Intertek Building & Construction (B&C), was contracted by ASI to perform heat flow meter testing in accordance with ASTM C518-21 on their, Acoustic Panel. Results obtained are tested values and were secured by using the designated test method. Testing was conducted at the Intertek B&C test facility in York, Pennsylvania.

Intertek B&C is an accredited testing laboratory and all testing was conducted in full compliance with ASTM approved procedures and specifications.

Intertek B&C will service this report for the entire test record retention period. The test record retention period ends four years after the test date. Test records, such as detailed drawings, datasheets, or other pertinent project documentation, will be retained for the entire test record retention period. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

For INTERTEK B&C:

**COMPLETED BY:** Benjamin W. Green

**TITLE:** Project Lead

**SIGNATURE:**

  
Digitally Signed by: Benjamin W. Green

**DATE:** 05/23/22

BWG:bwg

**REVIEWED BY:** Eric S. Leitner

**TITLE:** Manager - Thermal Testing

**SIGNATURE:**

  
Digitally Signed by: Eric S. Leitner

**DATE:** 05/23/22

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

## TEST REPORT FOR ASI

Report No.: N6822.01-116-25 R0

Date: 05/23/22

## SECTION 2

### TEST METHODS

The product were evaluated in accordance with the following:

**ASTM C518-21**, *Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus*

## SECTION 3

### TEST SPECIMEN DESCRIPTION

<b>SERIES/MODEL</b>	Cementitious Wood Fiber Acoustic Panel - 1" Thick
<b>PRODUCT TYPE</b>	Acoustic Panel
<b>SPECIMEN TEST SIZE</b>	12" x 12"

*\*This product is not a compressible sample.*

<b>SPECIMEN CONSTRUCTION</b>	The test specimens were provided by the client as three panels measuring approximately 1" x 12" x 12". The panels were tested as provided. See Appendix B: Photographs.
------------------------------	---

## SECTION 4

### TEST CONDITIONS

<b>COLD PLATE TEMPERATURE</b>	50°F nominal
<b>WARM PLATE TEMPERATURE</b>	100°F nominal
<b>MEAN SPECIMEN TEMPERATURE</b>	75°F nominal
<b>AVERAGE TEMPERATURE GRADIENT</b>	50°F/inch nominal
<b>HEAT FLOW ORIENTATION</b>	Vertical Heat Flow, The specimen was prepared and installed into the test apparatus horizontally so that the measured heat flow was from the hot plate to the cold plate, as intended for use.
<b>SPECIMEN CONFIGURATION</b>	Single horizontal specimen
<b>METERING AREA</b>	4" x 4" heat flux transducer on warm side plate

## TEST REPORT FOR ASI

Report No.: N6822.01-116-25 R0

Date: 05/23/22

### SECTION 5 EQUIPMENT

DESCRIPTION	SERIAL #	ASSET #	CALIBRATION DATE
Dial Calipers (0-12")	52-008-012-0	INT01848	01/18/23
Adams Scale (CBK 70A)	17960300	65197	12/15/22
Digital Indicators (0-1")	17960305	65196	01/14/23
Temp/Humidity Transmitter	12961265	63736	02/24/23
LC2 - LaserComp Fox304	13091619-F304	65203	*

\*Device calibrated prior to use.

### SECTION 6 CALIBRATION INFORMATION

Calibration Material	NIST Standard Reference Material 1450d, 1" Thickness Fibrous Glass Board, Serial Number 357, dated January 20, 2012, no expiration.	
Material Thermal Conductance	0.228	(C) (Btu/hr-ft <sup>2</sup> ·°F)

### SECTION 7 TEST RESULTS (IP Units)

Test Specimen ID	Sample Name	Avg. Heat Flux (Btu/hr-ft <sup>2</sup> )	Avg. Thermal Conductance (C) (Btu/hr-ft <sup>2</sup> ·°F)	Avg. Thermal Resistance (R) (hr-ft <sup>2</sup> ·°F/Btu)	Avg. Thermal Resistivity (r) (hr-ft <sup>2</sup> ·°F/Btu-in)	Apparent Thermal Conductivity (k) (Btu-in/hr-ft <sup>2</sup> ·°F)	Specimen Avg. Thickness (inches)	†Specimen Avg. Density (Lbs/Ft <sup>3</sup> )
1	Sample 1	21.63	0.432	2.31	2.35	0.425	0.983	21.63
2	Sample 2	21.95	0.438	2.28	2.33	0.429	0.978	21.90
3	Sample 3	21.21	0.424	2.36	2.39	0.418	0.985	22.85

**TEST REPORT FOR ASI**

Report No.: N6822.01-116-25 R0

Date: 05/23/22

**SECTION 7 (continued)**

**TEST RESULTS (SI Units)**

Test Specimen ID	Sample Name	Avg. Heat Flux (W/m <sup>2</sup> )	Avg. Thermal Conductance (C) (W/m <sup>2</sup> ·K)	Avg. Thermal Resistance (Rsi) (m <sup>2</sup> ·K/W)	Avg. Thermal Resistivity (r) (m·K/W)	Apparent Thermal Conductivity (k) (W/m·K)	Specimen Avg. Thickness (mm)	†Specimen Avg. Density (kg/m <sup>3</sup> )
1	Sample 1	68.23	2.453	0.41	16.33	0.061	24.97	346.54
2	Sample 2	69.24	2.489	0.40	16.17	0.062	24.84	350.84
3	Sample 3	66.92	2.408	0.42	16.60	0.060	25.02	366.09

†The density of the sample was determined by dividing the average weight of the sample by its volume. The weight was measured using a calibrated scale and the volume was determined by measuring the length, width, and height of the sample.

ANSI/NCSL Z540-2-1997 Type B uncertainty for this test was: 4%

**TEST REPORT FOR ASI**

Report No.: N6822.01-116-25 R0

Date: 05/23/22

**SECTION 8**

**PICTURES**

Cementitious Wood Fiber Acoustic Panel - 1" Thick, (Sample 1)





**TEST REPORT FOR ASI**

Report No.: N6822.01-116-25 R0

Date: 05/23/22

**SECTION 8 (continued)**

**PICTURES**

Cementitious Wood Fiber Acoustic Panel - 1" Thick, (Sample 2)





**TEST REPORT FOR ASI**

Report No.: N6822.01-116-25 R0

Date: 05/23/22

**SECTION 8 (continued)**

**PICTURES**

Cementitious Wood Fiber Acoustic Panel - 1" Thick, (Sample 3)



**TEST REPORT FOR ASI**

Report No.: N6822.01-116-25 R0

Date: 05/23/22

**SECTION 9**

**REVISION LOG**

REVISION #	DATE	PAGES	REVISION
.01 R0	05/23/22	N/A	Original Report Issued to Customer.